

www.phigroup.co.uk

Robert Torrington—Business Development Director

01242 707600 robert.torrington@phigroup.co.uk

Development: Lakeside View, Westbury, Wiltshire

Solution: Permacrib Timber Crib Retaining Wall

Region: DWH South West, Bristol



Phi Group were employed directly by DWH South West to design, supply & install 3 No. Permacrib timber crib retaining wall at their Lakeside View Development in Westbury, Wiltshire.

Phi Group has designed, supplied and installed the BBA Certified Permacrib timber crib retaining wall system for over 30 years.



Over two phases, Phi Group installed 3 no. Permacrib timber crib walls, including 1.80 close boarded fencing and access steps.

In total the three walls were 190m in length with a face area of 400m² and a maximum retained height of 3.50m

The overall project value was circa £90K.

Phi Groups works included:

- Fully indemnified design
- Supply of Permacrib components
- Supply & placement of the concrete foundation
- Supply and placement of granular infill stone
- Installation of timber access steps



Additional works that Phi Group can undertake

- Excavation
- Supply, Placement & compaction of granular backfill material
- Installation of timber fencing, Both post and three rail and 1.80m close boarded.
- Typically Phi Group will work in conjunction with a nominated ground worker on site, but we are also fully capable of expanding our scope of works when required.

